

AS100/A



- Fully automatic
- Capacity up to **220.46 lb**
- Power kw 1.3 - V. 220/125 Hz 60
- Size 4.66 x 2.79 x H 6.66 ft

Touch screen control unit.



- n° 20 weekly differentiated programs
- Touch screen graphic controller
- Display: resolution of 800x600
- The resistive touch screen extremely sensible makes the use of the tool easy and immediate.
- 5 digital input
- 4 analog input 4-20mA / PT100
- 1 USB Server input
- 1 USB Client input
- 1 LAN/TCP/IP plug
- 1 Memory Card MICRO-SD (not included)
- 1 RS485 (expansion MI212 + MI500)
- 1 RS232

Electronic control unit for the temperature and humidity control at weekly phases automatically.



- Opportunity of parameters variation about temperature and humidity even during the running phase of a program
- Automatic and manual operation
- Big size and bright display for the real temperature and humidity
- Display for the time scheduling of the sets and work cycles.
- Hot air temperature control
- Heating command
- Cooling command
- Dehumidification command. Automatic left / right air handling
- Automatic and manual defrosting at hot gas
- Internal light switching on/off commands